

Abstract

The Watlow electric radiant panel that was used as the heat source in the chamber for testing thermal/acoustical insulation was discontinued in April 2010. Power Modules Incorporated has been fabricating the electric radiant panel now used in the test chamber, since May 2010.

Additionally, the Series 93 controller, which was supplied with the original electric panel, was phased out in June of 2010. This controller was replaced by the Ez-Zone PM controller. This presentation will discuss the operation of the new panel and the differences between the Ez-Zone PM and the Series 93 controller.